RIGHT SIDE ELEVATION

AREA CALCULATION FOR TYPICAL FLOOR

AREA OF BLOCK = 72.84 X 14.15 = 1030.69 SQM

DEDUCTIONS

1. 6.10 X 1.50 = 9.15
2. 2.20 X 2.20 = 4.84
3. 2.55 X 1.20 = 3.06
4. 4.71 X 4.73 = 22.28
5. 1.75 X 1.60 = 2.80
6. 2.55 X 1.20 = 3.06
7. 4.71 X 4.73 = 22.28

TOTAL = 67.47

NET AREA = 1030.69 - 67.47 = 963.22 SQM



LOCATION PLAN



SITE PLAN

PLOT AREA CALCULATION

CALCULATION FOR S.NO. 46/20, 46/21

1. 0.5 X 160.34 X 6.35 = 318.69
2. 0.5 X 103.15 X 6.06 = 312.54
3. 0.5 X 97.95 X 11.85 = 580.89
4. 0.5 X 97.61 X 12.25 = 597.56
5. 0.5 X 3.53 X 0.97 = 1.31
6. 0.5 X 1.63 X 0.65 = 0.51

TOTAL = 1811.59

TOTAL SITE AREA BY TRIANGULATION	= 1811.59 SQM.
TOTAL SITE AREA BY 7/12 OR DOCUMENT	= 1811.59 SQM.
MIN. ARE CONSIDERED AS SITE AREA	= 1811.59 SQM.
NET PLOT AREA	= 1811.59 SQM.



AREA STATEMENT

FLOOR	PROPOSED FLOOR AREA IN SQM
GROUND FLOOR	359.00
FIRST FLOOR	1023.00
SECOND FLOOR	980.00
THIRD FLOOR	980.00
FOURTH FLOOR	980.00
FIFTH FLOOR	980.00
SIXTH FLOOR	980.00
SEVENTH FLOOR	980.00
EIGHTH FLOOR	194.00
TOTAL	7456.00

NOTES :

1. ALL DIMENSIONS ARE IN METERS.
2. FLOOR TO FLOOR HEIGHT = 3.65 M
3. ONLY PARKING FLOOR HEIGHT = 4.25 M
4. BUILDING IS P + 8 FLOORS
5. CONSIDERED ADDITIONAL LOAD OF 7TH FLOOR
6. TOILET SUNK 200 MM
7. EVERY WINDOW SHALL HAVE 0.15 M WEATHERSHIE RCC PROJ.
8. TYPICAL FLOOR COLUMN SIZES REFER RCC CONSULTANT'S DRG.

DOOR WINDOW SCHEDULE

SCHEDULE OF DOOR & WINDOWS	
OPENING	SIZE
DOORS	
D1	1.00 X 2.30
D2	0.75 X 2.30
WINDOWS	
OPENING	SIZE
W1	1.20 x 1.20
W2	1.80 x 1.20
W3	2.40 x 0.90
V	0.60 0.60

STAMP OF APPROVAL 1/2

ગ્રામપંચાયત કાર્યાલય નરહુર-નરસાપુર રસ્તાપર
નરસાપુરાનારોડ ઉપરનરહુર ગામની હદમાં
બાંધકામ વગર ગામ નકશા મંજુર કરવામાં
આવેલ છે. જે બાંધકામ ગામ નકશા મંજુર
કરેલ નકશા મુજબ જ બાંધકામ કરવાનું રહેશે.
ફેરફાર કરવાનો થશે તો ફરીથી નકશો
મંજુર કરાવવાનો રહેશે.

સરપંચ
ગ્રામપંચાયત ઓફિસ
તા. હવેલી, જિ. પુણે

True Copy
Architect
Signature

AREA STATEMENT

1	AREA OF PLOT AS PER 7/12 ABSTRACT	1811.59
	AREA OF PLOT AS PER DEMARCTION	1811.59
	MINIMUM TO BE CONSIDERED	1811.59
2	DEDUCTIONS FOR	
	a. ROAD WIDENING AREA	NA
	b. PROPOSED INTERNAL ROAD	NA
	c. ANY RESERVATION	NA
	TOTAL (a + b + c)	NA
3	NET GROSS AREA OF PLOT	1811.59
4	DEDUCTIONS FOR	
	a. RECREATIONAL GROUND (10%)	NA
	b. INTERNAL ROADS	NA
	TOTAL (a + b)	NA
5	NET AREA OF PLOT (3-4c)	1811.59
6	ADDITION FOR F.A.R.	NA
7	TOTAL AREA OF (5 + 6)	1811.59
8	F.A.R. PERMISSIBLE (0.75)	NA
9	PERMISSIBLE FLOOR AREA (8c7)	NA
	a. EXISTING FLOOR AREA	NA
	b. PROPOSED FLOOR AREA	7456.00
	c. EXCESS BALCONY AREA TAKEN IN F.S.I.	NA
	d. EXCESS PASSAGE AREA TAKEN IN F.S.I.	NA
10	TOTAL BUILT UP AREA PROPOSED (a+b+c+d)	NA
11	F.A.R. CONSUMED (10/9)	NA

12 BALCONY STATEMENT

NET PROPOSED ON ALL FLOORS	FLOOR AREA	15% PERMISSIBLE BALCONY	EXISTING BALCONY AREA	PROPOSED BALCONY AREA	TOTAL EXCESS BALC AREA
NA		NA	NA	NA	NA
13	EXCESS BALCONY IN F.S.I.				
NA		NA	NA	NA	NA

14 PARKING STATEMENT

	CARS	SCOOTERS	CYCLES
PARKING REQUIRED BY RULES	61	02	06
PARKING PROPOSED = 6242.54	89	125	500

15 GROUND COVERAGE STATEMENT

NET PLOT AREA	1811.59
LESS AMENITY / OPEN SPACE AREA	---
PERMISSIBLE GROUND COVERAGE (50%)	1405.15
PROPOSED GROUND COVERAGE	973.03
BALANCED GROUND COVERAGE	

PROJECT

PROPOSED EDUCATIONAL BUILDING,
AT S.NO. 46/20,46/21,
VILLAGE - NARHE, TAL - HAVELI, DIST - PUNE.

OWNER

LATE UDHAVRAO TULSIRAM JADHAVAR FOUNDATION, PUNE.

President
Late Udhavrao Tulshiram Jadhavar
Foundation, Indraprasth, Krantinagar,
Wadgaon Bk., Pune-41

DATE	SCALE	DRAWN BY
	1:100	NA

FOR DESIGNERS GROUP PUNE

NOTE : THIS DRAWING IS NOT AS PER THE RULES AND REGULATIONS. THIS IS PREPARED TO OBTAIN PLANNING PERMISSION. THIS DRAWING IS NOT FOR ANY KIND OF EXAMINATION AND SANCTION IF IT IS SO SUBMITTED, THE ARCHITECT IS NOT RESPONSIBLE FOR ANY KIND OF ISSUES LIKE MISCHIEVOUS, FINANCIAL, LEGAL, DEMAND, CONSTRUCTION ON SITE ETC.